


INSULATION NOTE
 ALL STEAM SUPPLY LINES SHALL BE INSULATED PER SCHEDULE SHOWN IN DETAIL SHEET AT QUANTITY SHOWN. IF HEADER SO AS TO NOT RESTRICT MOVEMENT AT QUANTITY.

- NOTES:**
- 1) ALL ITEMS WITHIN BATTERY LIMITS (DASHED LINES) SUPPLIED BY VENDOR. CONTRACTOR/INSTALLER SHALL COMPLY WITH MANUFACTURER DESIGNS, RECOMMENDATIONS AND MANUALS, AND CONFORM TO APPLICABLE CODES.
 - 2) SAFETY RELIEF VALVES SUPPLIED WITH BOILER, VESSELS, AND FEEDWATER TANK SHALL BE PIPED PER TYPICAL DETAIL THIS SHEET. CONTRACTOR SHALL SUPPLY DRAIN PAN ELBOW ASSEMBLIES FOR EACH SRV.
 - 3) PIPING CONTRACTOR SHALL FIELD VERIFY LOCATIONS AND DIMENSIONS - DIMENSIONS INCLUDED HERE FOR MAT'L TAKEOFF ONLY.
 - 4) TAGGED LINES AND INSTRUMENTS THIS SHEET SHALL BE SUPPLIED BY CONTRACTOR, UNLESS OTHERWISE SPECIFIED. WORK THIS SHEET WITH OTHER DRAWINGS. SEE SHEETS L1 & L2 FOR SPECIFICATIONS, QUANTITIES AND TAG IDENTIFICATION.



RELIEF/SAFETY VALVE VENT PIPING DETAIL